17	Providing and fixing of 50mm GI Nipple to motor Complete as per Specification.	No's	4.00	104.30	Rupees One Hundred Four and Thirty Paise Only
18	Providing and fixing of 50mm GI union to the motor Complete as per Specification.	No's	4.00	223.70	Rupees Two Hundred Twenty Three and Seventy Paise Only
19	Labour Charges for end connection Complete as per Specification.	No's	2.00	400.00	Rupees Four Hundred Only
20	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) Complete as per Specification.	Per length	108.00	88.00	Rupees Eighty Eight Only
21	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc,. Complete as per Specification.	No's	2.00	475.00	Rupees Four Hundred Seventy Five Only
22	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP Complete as per Specification.	No's	2.00	880.00	Rupees Eight Hundred Eighty Only
23	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) Complete as per Specification.\	Mtr	60.00	165.00	Rupees One Hundred Sixty Five Only
24	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces Complete as per Specification.	Mtr	60.00	55.00	Rupees Fifty Five Only
25	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm Complete as per Specification.	Mtr	4.00	286.00	Rupees Two Hundred Eighty Six Only
26	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc,. is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia Complete as per Specification.	No's	2.00	1650.00	Rupees One Thousand Six Hundred Fifty Only